

Field Notes of the survey of the exterior lines of Tp. 3 N., R. 36 E., by William H. Odell, under his contract No. 114, dated July 2, 1866. (N. bdy. T.2 N., R. 36 E.)

Chains		
	Begin at the South West corner	
	Thence	
	East on south boundary of section 31.	
17.00	Summit of ridge, course N. E.	+200
40.00	Set basalt stone 7 x 8 x 15 on steep hillside for $\frac{1}{4}$ sec. corner.	-200
53.00	Meacham Creek, 30 lks. wide, course N.E.	-175
63.50	" " " " " " S.E.	
76.00	" " " " " " N.E.	
80.00	Set post corner for sections 31, 32, 5 & 6, from which A pine, 24 ins. in diam. bears S.50° W. 19 lks. " " 16 " " " " N.60° W. 31 " " " 18 " " " " N.15° E. 30 lks. No tree near in section 5. This line passes over very broken lands, quite rocky; some pine timber along creek bottom.	+20
	East on south boundary of section 32.	
	Var. 21°30' East.	
40.00	Set post corner for $\frac{1}{4}$ Section on steep hill side facing the South West, made stone mound as per instructions.	+150
	Var. 20° East.	
80.00	Set post corner for sections 32, 33, 4 & 5; drove charred stake and made stone mound as per instructions. Land, broken and rocky. A very good grove of timber on Northwest quarter of section 5, T. 2, N. R. 36 E.; timber small growth fir, larch and pine.	+50
	East on south boundary of section 33.	
	Var. 20° 45' East.	
20.00	Summit of ridge, course N.W.	+300
40.00	Set post corner for $\frac{1}{4}$ section in ravine, course N.W. Drove charred stake, dug pits and raised mound as per instructions.	-100
48.00	Summit of ridge, course North.	+125