

Chains

East on South boundary of section 36.

Var. 20° East.

40.00 Set post corner for $\frac{1}{4}$ section on mountain side facing the West, drove charred stake, dug pits and raised mound, as per instructions. †700

80.00 For Townships 2 & 3 North, Ranges 36 & 37, East, sections 1, 6, 31 & 36, a fir, 24 ins. in diam. was made for corner, from which, †100

A fir 20 ins. in diam. bears S.20° W. 21 lks.

" " 18 " " " " N.30° W. 65 lks.

" " 16 " " " " N.65° E. 40 lks.

No tree near in section 6.

This line passes up the mountain. The corner is near the summit of the Blue Mountains. The last 20.00 chs. through timber, fir, larch and pine; undergrowth, the same with willow.

September 3rd, 1866.

Extracts from Subdivisions, T. 3,N.,R.36 E.
Survey by George L. Pershin, under his contract
No. 305, dated Sept. 20, 1878.

After diligent and careful search, I can find no trace of corner to sections 34 and 35. I, therefore, return to the corner of sections 35 and 36 and I run

West along the south boundary of sec. 35.

Var. 18° 45' East.

37.50 Spring branch, course S.W. -450

58.00 " " " S.W. -100

71.00 Brook, 20 lks. wide, course N.W. Also, enter timber. -100

80.00 Set stone 14 x 10 x 7 on North hillside for corner to secs. †80
34, 35, 2 and 3, from which,

A fir, 12 ins. in diam. bears N.82° E., 164 lks. dist.

A pine, 14 " " " " S.80° E., 167 " "

A pine, 4 " " " " S. 72°W., 21 " "

No tree in sec. 34.
