

## Subdivisions, T. 2 N., R. 36 E.

## Chains

	<p>A fir, 12 ins. in diam. bears N.14° E., 32 lks. dist., marked T 2 N R 36 E. S 15 B T.</p> <p>A pine, 6 ins. in diam. bears S. 35° E. 59 lks. dist., marked T 2 N.R 36 E. S22 B. T.</p> <p>A pine, 28 ins. in diam. bears S. 13° W. 133 lks. dist., marked T.2 N. R 36 E. S21 B.T.;</p> <p>no other tree within limits and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Timber, scattering fir, tamarack and pine.</p>
	<p>East on a random line bet. secs. 15 &amp; 22. Var. 19-3/4° E.</p> <p>Ascend about 25 ft. to</p>
2.50	Top of ridge, course N.W.
	Descend about 800 ft. to
33.00	Bottom of canyon and dry bed of creek, course N.
40.00	Set temporary 1/4 sec. cor.
80.76	Top of hill, about 800 ft. above canyon, course N. Intersect 40 lks. S. of the cor. to secs. 14, 15, 22 & 23.
	Thence, I run
	S. 89° 43' W. on a true line bet. secs. 15 & 22.
40.38	Set a basalt stone 15 x 10 x 7 ins., 10 ins. in the ground for 1/4 sec. cor., marked 1/4 on N. face, from which, A fir, 24 ins. in diam. bears S. 85° E. 207 lks. dist., marked 1/4 S. B. T, no other tree within limits and raised a mound of stone alongside.
80.76	The cor. to secs. 15, 16, 21 & 22. Land, mountainous. Soil, stony, 3rd rate. Timber, scattering fir, pine and tamarack.