

Subdivisions, T. 2 N., R. 36 E.

Chains	
	Dry bed of creek, course N.W.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
43.50	Top of ridge, about 250 ft. above gulch, course N.W.
58.00	Bottom of gulch, about 100 ft. below ridge, course N.W.
80.76	Intersect 75 lks. S. of the cor. to secs. 15, 16, 21 & 22.
	Thence, I run
	S. 89° 28' W. on a true line bet. secs. 16 and 21.
40.38	Set a basalt stone 13 x 10 x 8 ins., 9 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.
80.76	The cor. to secs. 16, 17, 20 & 21.
	Land, mountainous.
	Soil, stony, 3rd rate.
	Timber, scattering pine, fir and tamarack.
From the cor. to secs. 31 & 32, which is a post 4 ft. long, 4 ins. square, 24 ins. in the ground, marked: T 2 N R 36 E S32 on N.E.; T 1 N R 36 E S5 on S.E.; T 1 N R 36 E S 6 on S.W.; T 2 N R 36 E S31 on N.W. faces, with 5 notches on E. and 1 notch on W. edges, from which	
	a fir, 26 ins. in diam. bears N. 70° E., 8 lks. dist., marked T 2 N R 36 E S32 B.T.
	A fir, 32 ins. in diam. bears S.35° E., 9 lks. dist., marked T 1 N R 36 E S5 B.T.
	A fir, 30 ins. in diam. bears S.33° W 35 lks dist., marked T 1 N R 36 E. S 6 B.T.
	A fir, 10 ins. in diam. bears N.63° W. 12 lks. dist., marked T 2 N R 36 E S31 B.T.
	I run,
	North bet. secs. 31 and 32.
	Var. 17 $\frac{1}{2}$ ° E.
	Descend about 700 ft. to
21.00	Foot of hill, course N.W.
26.00	Wagon road, course N.W.
31.25	Meacham Creek, 50 lks. wide, runs N.W.