

Subdivisions, T. 2 N., R. 36 E.

Chains	
52.10	Set a basalt stone 15 x 15 x 12 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised a mound of stone alongside.
92.10	The cor. to secs. 29, 30, 31 & 32. Land, mountainous except 13.25 chs. on creek bottom. Soil, sandy loam and stony, 2nd & 3rd rate. Timber, scattering fir and pine.
North bet. secs. 29 & 30.	
Var. 20° East.	
Along steep side hill.	
40.00	Set a basalt stone 16 x 14 x 8 ins., 11 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which A pine 15 ins. in diam. bears N. 45° E. 160 lks. dist., marked $\frac{1}{4}$ S. B. T.; no other tree within limits and raised a mound of stone alongside.
64.00	A spring branch, 2 lks. wide, runs W.
80.00	Set a basalt stone 12 x 10 x 6 ins., 8 ins. in the ground for cor. to secs. 19, 20, 29 & 30, marked with 2 notches on S. and 5 notches on E. edges, from which A fir, 7 ins. diam. bears S. 89° E. 55 lks. dist., marked T 2 N. R 36 E. S29, B. T.; no other tree within limits and raised mound of stone alongside. Land, steep and mountainous. Soil, stony, 3rd rate. Timber, scattering fir and pine. Good bunch grass.
East on a random line bet. secs. 20 and 29.	
Var. 19-3/4° East.	
Ascend mountain.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
63.75	Top of ridge, about 800 ft. above sec. cor., course N.W.