

Subdivisions, T. 2 N., R. 36 E.

Chains	
76.50	Bottom of gulch, about 500 ft. below ridge.
	Dry bed of creek, course N.W.
80.32	Intersect 25 lks. S. of the cor. to secs. 20, 21, 28 & 29.
	Thence, I run
	S. 89° 49' W. on a true line bet. secs. 20 & 29.
40.16	Set a basalt stone 14 x 9 x 8 ins., 9 ins. in the ground
	for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised a mound
	of stone alongside.
80.32	The cor. to secs. 19, 20, 29 & 30.
	Land, mountainous.
	Soil, 2nd rate.
	Timber. scattering fir and pine.
	.
	.
	.
	Knowing that I will strike the Umatilla Indian Reservation
	in less than a mile, I run
	West on a true line bet. secs. 19 & 30.
	Var. 19 $\frac{1}{2}$ ° East.
	Descend mountain.
20.00	Foot of hill, about 700 ft. below cor. N.
20.25	Intersect graded road bed of the Baker City Railway line,
	course N. 10° East.
21.00	Wagon road, course N. 10° East.
23.50	Meacham Creek, 50 lks. wide, runs N.
33.00	Ascend mountain, course N.
40.00	Set a basalt stone 15 x 10 x 9 ins., 10 ins. in the
	ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on N. face, from
	which
	A fir, 14 ins. in diam. bears N. 40° E. 28 lks.
	dist., marked $\frac{1}{4}$ S. B. T.
	A fir, 20 ins. in diam. bears S. 5° E. 13 lks. dist.,
	marked $\frac{1}{4}$ S. B. T.
	I can find no trace of the line to the Umatilla Indian
	Reservation. I, therefore, discontinue this line at
	this point.
	Land, mountainous except 13.00 chs. on Meacham Creek,