

T. 2 N., R. 36 East...

Chains	
59.50	Top of ridge, 150 ft. high, course N.W. and S.E. Descend.
63.56	Intersect the closing cor. of secs. 4 and 5, established by me July 3d, 1901.
82.40	Intersect the old cor. of secs. 32 and 33, described heretofore.
	Land, mountainous.
	Soil, 3rd rate.
	Timber, fir, pine, wild cherry and tamarack.
	Undergrowth, mountain laurel and wild cherry.
	Mountainous land, 82.40 chs.
	July 4, 1901.
<p>East boundary T. 2, N., R. 36 E. I commence at the cor. of tps. 1 and 2, N., Rs. 36 and 37 E., described heretofore,</p>	
	Thence, I run
	North bet. secs. 31 and 36 on old township line.
	Ascend S. slope of ridge through heavy timber and dense undergrowth.
3.50	Leave timber and undergrowth and pass over rocky prairie, bears E and W.
10.00	Top of ridge, 100 ft. above Tp. cor., bears E and W. Descend N. slope of mountain.
11.00	Steeper descent through heavy pine and fir timber, bears E. and W.
33.00	Enter dense undergrowth, bears E. and W.
40.30	Intersect the old $\frac{1}{4}$ sec. cor., which is a post, badly decayed, marks obliterated and witnessed as described by the Surveyor General. I set a tamarack post, 3 ft. long, 3 ins. square, 24 ins. in the ground, at the same point, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S. 36 on the W. and S.31 on the E. faces.
45.00	Enter scattering timber, bears E and W.
46.15	John Smith's pack trail, bears E. and W.