

T. 2 N., R. 36 East W. M.

Chains	
	N. on true line bet. secs. 1 and 6.
	Ascend along W. slope of mountain through scattering timber and occasional patches of dense undergrowth.
35.00	Enter heavy timber, bears E. and W.
40.00	Set iron stone 12 x 8 x 8 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which
	A fir, 20 ins. in diam. bears N. 10° E., 47 lks. dist., marked $\frac{1}{4}$ S.6 B. T.
	A fir, 18 ins. in diam. bears S. 18° W., 9 lks. dist., marked $\frac{1}{4}$ S. 1, B. T.
	This cor. stands about 300 ft. above sec. cor.
48.00	Leave timber, bears E. and S. 60° W.
57.00	Summit of main divide bet. Umatilla River and Meacham Creek, 1800 ft. above Umatilla River, bears N. 10° E., S. 60° W.
	Pass along level summit of mountain.
61.20	Trail to Gibbon, course N. 10° E., S. 60° W.
70.20	Enter heavy pine and fir timber, bears N.60° W., S.30° E.
	Descend gradually N. slope of mountain.
71.59	Intersect Tp. line 24.84 chs. E. of the S.W. cor. of T.3 N., R. 37 E.
	Set basalt stone 15 x 12 x 8 ins., 10 ins. in the ground for closing cor. of Tps. 2 N., Rs. 36 and 37 E., on S. bdy. of Tp. 3 N., R. 37 E., I marked with closing cor. on S., and with 6 grooves on S., E., and W. faces, from which,
	A fir, 10 ins. in diam. bears S. 45° E., 28 lks. dist., marked T. 2 N., R. 37 E., S.6, B. T.
	A fir, 12 ins. in diam. bears S. 50° W., 39 lks. dist., marked T. 2 N., R. 36 E., S. 1, B. T.
	Note: I destroy all marks on the S.W. cor. of Tp. 3 N., R. 37 E., which is a fir, 24 ins. diam., marked and witnessed as described by the Surveyor General, that pertain to Tps. 2 N., Rs. 36 and 37 E.