

Subdivisions, T. 2, N., R. 36 E.

Chains	
77.00	More gradual ascent.
77.40	Trail, bears N. 30° W., S. 30° E.
80.00	Set ironstone, 24 x 18 x 12 ins., 19 ins. in the ground for cor. of secs. 10, 11, 14 and 15, marked with 4 notches on S. and 2 notches on E. edges; raise mound of stone, 3 ft. base, 1½ ft. high, W. of cor. Pits impracticable.
	Land, level and mountainous.
	Soil, loam and stony, 1st and 4th rate.
	Timber, pine, fir and tamarack.
	Undergrowth, huckleberry, laurel and willows.
	Mountainous or densely overgrown land 80.00 chs.
	June 22: At 3 <sup><u>h</u></sup> - 10 <sup><u>m</u></sup> p. m., l. m. t., I set off 45° 40' on the lat. arc; 23° 27' N. on the decl. arc; and determine a true meridian with the solar at the cor. of secs. 10, 11, 14 and 15.
	Thence, I run
	W. on sectional correction line, bet. secs. 10 and 15.
	Ascend gradually over ridge.
1.50	Summit of ridge, 300 ft. above creek, bears N. 30° W., S. 30° E.
	Descend into Rine Creek.
12.00	Steeper descent - scattering patches of dense undergrowth.
35.00	Enter scattering timber, bears N. and S.
40.00	Set basalt stone 15 x 12 x 8 ins., 10 ins. in the ground for ¼ sec. cor., marked ¼ on N. face. No trees in limits; raise mound of stone, 2 ft. base, 1½ ft. high N. of cor. Pits impracticable.
56.40	Foot of mountain, bears N. and S.
	Pass over heavily timbered bottom, not subject to inundation.
57.50	Rine Creek, 20 lks. wide, swift current pure water, course N. 40° W.
	Ascend steep E. slope of ridge.
62.50	Enter scattering timber, bears N. and S.