

Subdivisions, T. 2 N., R. 36 E.

Chains	
46.00	<p>Ascend S. slope of ridge.</p> <p>Leave timber and pass through dense undergrowth, bears N.30° E., S. 60° W.</p>
50.00	<p>Leave undergrowth, bears E. and W.</p>
78.00	<p>Summit of ridge, 300 ft. above creek, bears E. and W.</p> <p>Descend steep N. slope.</p>
78.75	<p>Enter dense undergrowth, bears E. and W. Very scattering timber.</p>
80.00	<p>Set basalt stone, 20 x 15 x 5 ins., 15 ins. in the ground for cor. of secs. 2, 3, 10 and 11, marked with 2 notches on E. and 5 notches on S. edges, from which</p> <p>A fir, 10 ins. in diam., bears N. 18° E., 23 lks. dist., marked T. 2 N., R.36 E., S.2, B.T.</p> <p>No other trees in limits. Raise mound of stone, 2 ft. base, 1½ ft. high, W. of cor. Pits impracticable.</p> <p>Land, mountainous.</p> <p>Soil, stony and gravelly, 4th and 3rd rate.</p> <p>Timber, pine, fir, alder and willow.</p> <p>Undergrowth, willow, small firs, mountain laurel and vine maple.</p> <p>Mountainous land, 80.00 chs.</p>
40.00	<p>E. on random line bet. secs. 2 and 11.</p> <p>Set temp. ¼ sec. cor.</p>
79.78	<p>Intersect N. and S. line 30 lks. S. of the cor. of secs. 1, 2, 11 and 12.</p> <p>Thence, I run</p>
39.89	<p>S. 89° 49' W. on true line bet. secs. 2 and 11.</p> <p>Ascend gradually, along steep N. slope of ridge, through scattering timber and dense undergrowth.</p> <p>Set basalt stone, 15 x 8 x 6 ins., 10 ins. in the ground for ¼ sec. cor., marked ¼ on N. face, from which</p> <p>A fir, 5 ins., bears N. 10° E., 11 lks. dist., marked ½ S. 2, B. T.</p> <p>A fir, 10 ins. in diam., bears S. 31° E., 23 lks. dist., marked ¼ S. 11, B.T.</p>