

Subdivisions, T. 2 N., R. 36 E.

Chains	
	<p>Thence, I run N. 89° 54' W. on true line bet. secs. 4 and 9. Ascend steep slope of mountain, bears N. 10 W., S. 10° E., through scattering timber.</p>
7.50	Enter dense undergrowth, bears N. and S.
14.25	Leave timber and undergrowth, bears N. and S.
31.25	Divide bet. Rine Creek and Meacham Creek, 500 ft. above Rine Creek, bears N. 20° W., and S.
33.75	Pack trail to Gibbons, bears N. 10° W., S. 20° E. Descend W. slope of ridge.
39.90	Set basalt stone, 20 x 12 x 8 ins., 15 ins. in ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face. Raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N. of cor. Pits imprac- ticable.
74.00	Ravine, 200 ft. deep, course N. 70° W. Enter timber and dense undergrowth, bears N. 70° W., S. 70° E.
79.80	The cor. of secs. 4, 5, 8 and 9. Land, mountainous. Soil, stony and gravelly loam, 3rd and 2nd rate. Timber, pine, fir and tamarack. Undergrowth, mountain laurel, service berry, small tamarack and huckle berry. Mountainous lands, 79.80 chs. Overcast at noon prevented taking the latitude July 2, 1901.
	<hr/> <p>July 3; At 7^h 30^m A.M., l.m.t., I set off 45° 40.5' on the lat. arc, 23° 00' N. on the decl. arc and de- termine a true meridian with the solar at the cor. of secs. 4, 5, 8 and 9.</p>
	<p>Thence, I run N. 0° 04' W. on random line bet. secs. 4 and 5.</p>
40.00	Set temp. $\frac{1}{4}$ sec. cor.
70.48	Intersect the N. bdy. of Tp., 18.84 chs. E. of the cor.