

South Boundary of T. 3 N., R. 37 E.
 Surveyed by George S. Pershin, contract No. 304.
 Dated Sept. 19, 1878.

Chains	
	<p>I begin at the post, the corner to Townships 2 and 3 North, Ranges 36 and 37 East. The post is still standing and the witness trees I find as described in the field notes as furnished by the office viz:</p> <p>A fir, 20 ins. diam., bears S.20°W., 21 lks. dist. " " 18 " " " N.30°W., 65 " " " " 16 " " " N.65°E., 40 " "</p> <p>and with Burt's improved Solar Compass I run East along the South boundary of sec. 31. Var. 21°00'East.</p>
37.00	Begin to descend.
40.00	<p>Set fir post on East descent for $\frac{1}{4}$ sec. cor., from which, A spruce, 4 ins. diam., bears N.64°E., 10 lks. dist. " willow, 5 " " " S.15°E., 28 " "</p>
70.50	Leave timber, course N. and S.
80.00	<p>Set basalt stone, 14x10x8, on South side of spur extending -300 East for corner to sections 31, 32, 5 and 6, from which,</p> <p>A fir, 14 ins. diam., bears S.18°E., 197 lks. dist. " " 18 " " " S.8°W., 230 lks. dist.</p> <p>No other trees.</p> <p>Land, surface, on West 37 chs. nearly level, East 43 chs. very broken.</p> <p>Soil, 3rd rate.</p> <p>Some good timber on West 70 chs., remainder scattering pine, fir and tamarack.</p> <p>Some willow, alder and other underbrush.</p> <p>Note: There are several kinds of underbrush in this vicinity that I do not know any name for.</p>
	<p>East on South boundary of sec. 32. Var. 19°30'East.</p>
21.50	Spring branch, course N.E. and enter timber N.E. and S.W. -300
40.00	<p>Set basalt stone, 14x12x5, on North side of spur, for $\frac{1}{4}$ sec. cor.</p>