

## South Boundary of T. 3 N., R. 37 E.

Chains 80.00	<p>Set basalt stone, 18x14x8, on plateau in mound of stone for cor. to secs. 34, 35, 2 and 3.</p> <p>A pine, 30 ins. diam., bears N.55°E., 140 lks. dist.</p> <p>A pine, 10 ins. diam., bears S.50°E., 200 lks. dist.</p> <p>No other trees.</p> <p>Land, surface mountainous.</p> <p>Soil, 3rd rate.</p> <p>A few scattering pine and fir trees. Good bunch grass.</p>	+350
	<p>East along the South Boundary of sec. 35.</p> <p style="text-align: center;">Var. 20°30' East.</p>	
15.00	Begin to descend.	
40.00	<p>Set fir post on South hillside for <math>\frac{1}{4}</math> sec. cor.</p> <p>A fir, 4 ins. diam., bears N.55°W., 19 lks. dist.</p> <p>A fir, 12 ins. diam., bears S.62°E., 72 lks. dist.</p>	-100
78.00	Brook, 4 lks. wide, course N.W.	-200
80.00	<p>Set basalt stone, 16x8x7, on S.W. hillside, for corner to secs. 35, 36, 1 and 2, from which,</p> <p>A fir, 8 ins. diam., bears N.10°E., 60 lks. dist.</p> <p>" " 20 " " " S.24°E., 99 " "</p> <p>" " 36 " " " S.38°W., 66 " "</p> <p>" " 18 " " " N.68°W., 74 " "</p> <p>Land, surface mountainous.</p> <p>Soil, 3rd rate.</p> <p>Timber, good in places and in places scattering fir, tamarack and pine.</p> <p>Good grass in openings.</p> <p style="text-align: right;">April 15, 1879.</p>	+30
	<p>East on the South Boundary of sec. 36.</p> <p style="text-align: center;">Var. 22°30' East.</p>	
1.00	Leave timber, N.W. and S.E.	
36.00	Enter timber, N. and S.	
40.00	<p>Set spruce post on level for <math>\frac{1}{4}</math> sec. cor., from which,</p> <p>A spruce, 10 ins. diam., bears N.38°W., 18 lks. dist.</p> <p>A fir, 8 ins. diam., bears S.70°W., 15 lks. dist.</p>	+150