

South Boundary of T. 3 N., R. 37 E.

| | | |
|---|---|------|
| Chains | | |
| 67.00 | Spring branch, course N.W. | -100 |
| 78.00 | Leave timber, course N. and S. | |
| 80.00 | Set basalt stone, 18x10x8, in mound of stone on level open glade for corner to Townships 2 and 3 North, Ranges 37 and 38 East Willamette Meridian, from which, Fir, 28 ins. diam., bears S.24°W., 210 lks. dist. " 12 " " " N.46°W., 340 lks. " No other trees near. Land, surface mountainous. Soil, 3rd rate. Good timber on E. $\frac{1}{2}$ mile, W. $\frac{1}{2}$ mile scattering fir, tamarack and pine. | |
| Exterior of T. 2 N., R. 38 E. (West Boundary) Surveyed by Jacob C. Cooper under contract No. 397. Dated July 1st, 1881. | | |
| Thence North between secs. 31 and 36. Var. 20°15'E. Ascend slightly thru heavy timber and dense underbrush. | | |
| 7.50 | Descend slightly. | |
| 15.00 | Slight windfall and undergrowth. | |
| 34.00 | Ascend slightly and undergrowth. | |
| 37.50 | Descend. | |
| 40.00 | Set post 3 $\frac{1}{2}$ ft. long, 3 ins. square, marked $\frac{1}{4}$ S on E. and W. faces, for $\frac{1}{4}$ sec. cor. in heavy timber and undergrowth, sloping N.E. A fir, 12 ins. diam., bears N.31°E., 35 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 16 ins. diam., bears N.60°W., 37 lks. dist., marked $\frac{1}{4}$ S B T. | |
| 41.00 | Level, heavy timber. | |
| 45.00 | Ascend in heavy timber and dense undergrowth. | |
| 65.00 | Descend. | |
| 75.30 | Spring branch, course E. Ascend abruptly. | |
| 80.00 | Set post 4 ft. long, 4 ins. square, 2 ft. in ground, for cor. to secs. 25, 30, 31 and 36 on summit of ridge. | |