

West Boundary of T. 2 N., R. 38 E.

Chains	
	<p>Course of ridge East and West, 100 ft. above spring branch, summit of ridge open. Post is marked T 2 N S 30 on N.E., R 38 E S 31 on S.E., R 37 E S 36 on S.W. and S 25 on N.W. faces with 1 notch on S. and 5 notches on North edges.</p> <p>A pine, 30 ins. diam., bears S.22°E., 122 lks. dist., marked T 2 N R 38 E S 31 B T.</p> <p>A fir, 30 ins. diam., bears South 12°W., 110 lks. dist., marked T 2 N R 37 E S 36 B T.</p> <p>A fir, 26 ins. diam., bears N.40°W., 13 lks. dist., marked T 2 N R 37 E S 25 B T.</p> <p>A fir, 12 ins. diam., bears N.77°E., 22 lks. dist., marked T 2 N R 38 E S 30 B T.</p> <p>Land, a succession of ridges extend down to Willow Creek, which runs parallel with this line about $\frac{1}{2}$ mile to the East, this point is about 900 ft. above said creek.</p> <p>Soil, gravelly, 3rd rate.</p> <p>Timber, heavy fir, tamarack and pine.</p>
	<p>North between secs. 25 and 30.</p> <p style="text-align: center;">Var. 21°E.</p> <p>Descend heavy timber and very dense undergrowth.</p> <p>18.50 Spring branch, course E.</p> <p>Ascend abruptly.</p> <p>31.50 Summit of ridge, course E. and W.</p> <p>Descend thru dense young fir, spruce and tamarack.</p> <p>40.00 Set post $3\frac{1}{2}$ ft. long, 3 ins. square, $1\frac{1}{2}$ ft. in ground, marked $\frac{1}{4}$ S for $\frac{1}{4}$ sec. cor. on N.E. side of mountain, 100 ft. below summit.</p> <p>A fir, 22 ins. diam., bears S.10°E., 39 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir, 3 ins. diam., bears N.44°W., 18 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>52.50 Dry creek, course E.</p> <p>53.25 Summerville and warm springs road, course N.W. and S.E.</p> <p style="text-align: center;">Var. 23°E.</p>