

## West Boundary of T. 2 N., R. 38 E.

|                 |  |
|-----------------|--|
| Chains<br>70.00 | Enter timber and undergrowth.  |
| 80.00           | Set post on South hillside 4 ft. long, 4 ins. square, 2 ft. in ground, for cor. to secs. 13, 18, 19 and 24 marked T 2 N S 18 on N.E., R 38 E S 19 on S.E., R 37 E S 24 on S.W., S 13 on N.W. faces with 3 notches on N. and S. edges,<br><p style="margin-left: 40px;">A pine, 24 ins. diam., bears S.23°E., 19 lks. dist., marked T 2 N R 38 E S 19 B T.</p> <p style="margin-left: 40px;">A fir, 24 ins. diam., bears N.43°E., 46 lks. dist., marked T 2 N R 38 E S 18 B T.</p> <p style="margin-left: 40px;">A fir, 30 ins. diam., bears N.20°W., 40 lks. dist., marked T 2 N R 37 E S 13 B T.</p> <p style="margin-left: 40px;">A fir, 30 ins. diam., bears S.73°W., 98 lks. dist., marked T 2 N R 37 E S 24 B T.</p> <p>Land, high rolling and mountainous.<br/> Soil, gravelly, 3rd rate.<br/> Timber, fir, pine and tamarack.</p> |
|                 | North between secs. 13 and 18.<br><p style="text-align: center;">Var. 22°E.</p> Ascend thru large scattering pine and fir and dense chaparral.   |
| 6.00            | Summit of ridge, course East and West.<br>Descend.   |
| 19.75           | Bottom of ravine.<br>Ascend.   |
| 40.00           | Set post 3½ ft. long, 3 ins. square, 1½ ft. in ground, marked ¼ S on East and West faces, for ¼ sec. cor. on West side of summit of high ridge.<br><p style="margin-left: 40px;">A fir, 16 ins. diam., bears N.48°W., 54 lks. dist., marked ¼ S B T.</p> <p style="margin-left: 40px;">A pine, 18 ins. diam., bears S.73°E., 55 lks. dist., marked ¼ S B T.</p> <p style="text-align: center;">Var. 22°E.</p>  |
| 45.50           | Descend thru heavy pine and fir timber.  |
| 47.50           | Glade, 6.50 chs. wide; ascend.   |