

West Boundary of T. 2 N., R. 38 E.

Chains	
54.00	Enter timber; descend.
65.00	Spring branch, course N.75°West; ascend.
80.00	Set post on Southeast hillside in fir timber and dense undergrowth for cor. to secs. 7, 12, 13 and 18. Post, 4 ft. long, 4 ins. diam., 2 ft. in ground, marked T 2 N S 7 on N.E., R 38 E S 18 on S.E., R 37 E S 13 on S.W., and S 12 on N.W. faces with 2 notches on North and 4 notches on South edges, A fir, 16 ins. diam., bears S.37°W., 32 lks. dist., marked T 2 N R 37 E S 13 B T. A fir, 6 ins. diam., bears S.47°E., 58 lks. dist., marked T 2 N R 38 E S 18 B T. A fir, 6 ins. diam., bears N.67°W., 85 lks. dist., marked T 2 N R 37 E S 12 B T. A fir, 10 ins. diam., bears N.7°E., 44 lks. dist., marked T 2 N R 38 E S 7 B T. Land, mountainous and broken. Soil, gravelly, 4th rate. Timber, fir, pine, spruce and tamarack.
	North between secs. 7 and 12. Var. 18°30'E. Ascend.
15.00	Summit; descend. Enter glade.
20.50	Enter timber.
23.00	Bottom of ravine. Ascend thru heavy timber and dense undergrowth.
40.00	Set post 3½ ft. long, 3 ins. square, 1½ ft. in ground, marked ¼ S on W. and E. faces, for ¼ sec. cor. on S. side of summit of ridge at South margin of glade. A pine, 26 ins. diam., bears S.39°W., 64 lks. dist., marked ¼ S B T. A fir, 6 ins. diam., bears S.43°E., 32 lks. dist., marked ¼ S B T.