

Resurvey of South Bdy. of T. 3 N., R. 37 E.

Chains	
	<p>A pine, 48 ins. diam., bears N.28$\frac{1}{2}$°E., 1 ch. 29 lks. dist., marked T 3 N R 37 E S 35 B T.</p> <p>A pine, 12 ins. diam., bears N.22°10'W., 3 chs. 13 lks. dist., marked T 3 N R 37 E S 34 B T.</p> <p>No tree in limit.</p> <p>Raised mound of stone 2 ft. base, 1$\frac{1}{2}$ ft. high, N. of cor. Pits impracticable.</p> <p>The old cor. of secs. 34 and 35 bears N.37$\frac{1}{2}$°W., 1 ch. 2 lks. dist. I destroy all traces of this old sec. cor.</p> <p>Land, nearly level and mountainous.</p> <p>Soil, gravelly and stony, 3rd and 4th rate.</p> <p>Timber, pine, fir and tamarack.</p> <p>Undergrowth, pine, fir, tamarack, alder, willow, pine grass, huckleberry and bunchgrass.</p> <p>Good grazing land.</p> <p>Mountainous land, 59.75 chs.</p> <p style="text-align: center;">August 6, 1900.</p>
	<p>August 9: At 9.30 a.m., l.m.t., I set off 45°41'30" on the lat. arc., 15°52' 30" N. on the decl. arc. and determine a true meridian by the solar at the cor. of secs. 34 and 35.</p> <p>Thence I run</p> <p>N.89°44'W. on a true line S. bdy. of sec. 34.</p> <p>Descending along S. brow of mountain through scattering timber and undergrowth.</p> <p>8.00 Head of canyon, South; ascend, bears N.E. and S.W.</p> <p>15.00 Enter small copse on point, bears N.W. and S.E.</p> <p>18.50 Leave copse, thence over stony level through scattering timber.</p> <p>20.25 Leave point and descend gradually.</p> <p>27.50 Steeper descent, bears N.10°E. and S.10°W.</p> <p>28.25 Enter small timber and dense undergrowth.</p> <p>34.50 Leave timber and undergrowth; steep grassy descent across bend of canyon, S.W.</p> <p>37.25 Small, densely overgrown ravine, N.W.</p>