

Resurvey of South Edy. of T. 3 N., R. 37 E.

Chains	
38.75	Leave dense undergrowth; steep, grassy slope, N.20°W.
40.00	A point, 400 feet below the sec. cor. and set a basalt stone, 15x10x6 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N. of cor. Pits impracticable. After careful search fail to find any trace of the old $\frac{1}{4}$ sec. cor., described by the surveyor general as a stone, 20x12x4 ins., on N. side of ravine. No trees.
42.25	Enter dense undergrowth.
49.25	Stream, 2 lks. wide, runs S.70°W.; thence along steep N. side of ravine.
54.45	Leave dense undergrowth, steep slope S.
55.00	August 9: At this point I set off 15°50' 30" N. on the decl. arc., and at 0 h 5 m p.m., l.m.t., observe the sun on the meridian, the resulting lat. is 45°41' 30".
69.00	Narrow strip of undergrowth, bears N. and S.
75.25	Patch of undergrowth, bears N. and S.
80.00	A point, 350 feet below the $\frac{1}{4}$ sec. cor. and set a basalt stone, 15x6x5 ins., 10 ins. in the ground, for cor. of secs. 33 and 34, marked with 3 notches on E. and W. edges, and raised mound of stone 2 ft. base, $1\frac{1}{2}$ ft. high, N. of cor. Pits impracticable. The old cor. of secs. 33 and 34, a basalt stone, 18x12x10 ins., on S. face of ridge, bears S.86 $\frac{1}{2}$ °W., 1 ch. 28 lks. dist. I destroy all traces of this old sec. cor. Land, nearly level and mountainous. Soil, gravelly and stony, 3rd and 4th rates. Timber, scattering pine, fir and tamarack on first quarter. Undergrowth, pine, fir, tamarack, alder, willow, pine-grass, laurel, cherry, birch and bunch grass. Good pasturage. Mountainous land, 52.50 chs.
	N.89°44'W. on a true line, S. bdy. of sec. 33. Along steep, grassy S. slope.
4.00	Steeper descent into canyon of the South fork, bears N.W. and S.E.