

Resurvey of South Edy. of T. 3 N., R. 37 E.

Chains	
10.50	Enter scattering timber and undergrowth.
19.75	Very steep descent, bears N.10°W. and S.10°E.
22.50	Hill, bears N.80°W. and S.80°E.
30.00	Ascend steep hillside, bears N.80°E. and S.80°W.
37.00	Steep descent, bears N.20°W. and S.20°E.
40.00	A point, 500 feet below the sec. cor. and set a basalt stone, 20x8x4 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised mound of stone 2 ft. base, $1\frac{1}{2}$ feet high, N. of cor. Pits impracticable. Find no trace of the old $\frac{1}{4}$ sec. cor. described by the surveyor general as a stone, 18x8x7 ins., on S.W. hillside.
49.75	Enter timber and dense undergrowth, bears N. and S.
52.50	Down steep, bluff bank of river.
52.95	Seepage stream, 10 lks. wide, runs N.20°W.; cross stony, heavily timbered bar and bottom.
54.15	South fork of the Umatilla river, 15 lks. wide, pure water, flows N.20°W., over stony bed. Strong current.
56.90	Trail--old, abandoned wagon road, bears N. and S.E.
57.75	Stock trail up right-hand fork; bears N.70°E. and S.70°W.
59.40	Right hand fork, 75 lks. across, runs N.80°E. over stony, gravelly bottom.
61.00	Ascend steep, grassy hill, bears N.50°E. and S. 50°W.
65.75	Leave timber and cross lower end of open point, N.30°W.
67.00	Enter heavy timber, bears N.30°W. and S.30°E.
70.00	Steep, grassy ascent through scattering timber and undergrowth, bears N.70°E. and S.70°W.
77.50	Ravine, course S.30°E., steep ascent; bears N.10°E. and S.10°W.
80.00	A point about level with the $\frac{1}{4}$ sec. cor. and set an iron stone, 20x8x4 ins., 15 ins. in the ground, for cor. of secs. 32 and 33, marked with 4 notches on E. and 2 notches on W. edges, from which, A fir, 14 ins. diam., bears N.19°E., 1 ch. 69 lks. dist., marked T 3 N R 37 E S 33 B T.