

Resurvey of South Edy. of T. 3 N., R. 37 E.

Chains

A fir, 16 ins. diam., bears N.19°W., 1 ch. 74.lks. dist., marked T 3 N R 37 E S 32 B T.

The old cor. of secs. 32 and 33, a basalt stone, 14x10x5 ins., marked and witnessed as described by the surveyor general, bears N.89 $\frac{1}{4}$ °W., 1 ch. 25 lks. dist. I destroy all traces of this old sec. cor.

Land, level and mountainous.

Soil, part arable, sandy loam, gravel and stone, 2nd and 3rd and 4th rate.

Timber, pine, fir, tamarack and cottonwood.

Undergrowth, pine, fir, tamarack, alder, willow, cottonwood, cherry, pinegrass, service-berry and bunch grass.

Good pasturage.

Mountainous or heavily timbered land, 80.00 chs.

August 9, 1900.

August 10: At 9 a.m., l.m.t., I set off 45°41'30" on the lat. arc., 15°35'30" N. on the decl. arc., and determine a true meridian by the solar at the cor. of secs. 32 and 33.

Thence I run

N.89°44'W. on a true line, S. bdy. of sec. 32.

Ascending steep, grassy bank through scattering timber and undergrowth, bears N. and S.

2.50 Top of point, S.30°E.; descend, bears N.70°W. and S.70°E.

11.25 Leave timber on point, S.; steeper descent into canyon, bears N.30°W. and S.30°E.

18.75 Foot; boulder bed.

19.15 Branch of river, 10 lks. wide, runs S.30°E., over bed rock bottom; thence ascend steep bluffs through timber and dense undergrowth, bears N.40°W. and S.40°E.

26.50 Steep slope, N.

30.00 Ravine, course N.E. steep ascent, bears N. and S.

33.00 Leave dense undergrowth, thence scattering timber and heavy grass.