

## Resurvey of South Bdy. of T. 3 N., R. 37 E.

Chains 40.00	<p>A point 400 feet above the sec. cor. and set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor., marked <math>\frac{1}{4}</math> on N. face, from which,</p> <p>A fir, 14 ins. diam., bears N.61°E., 81 lks. dist., marked <math>\frac{1}{4}</math> S 32 B T.</p> <p>The old <math>\frac{1}{4}</math> sec. cor., a basalt stone, 14x12x5 ins., marked and witnessed as described by the surveyor general, bears S.84°W., 1 ch. 44 lks. dist. I destroy all traces of this old cor.</p>
40.25	Top of rock-ridge, N.60°E., descend through timber and dense undergrowth, bears N.75°E. and S.75°W.
42.00	Slope N.
45.00	Descend abruptly, bears N.60°E. and S.60°W.
48.25	Ravine, course N.20°E., steep ascent, bears N.10°W. and S.10°E.
50.50	Top of rise or point, N.E.; descend.
57.75	Foot.
58.00	Rill, 1 lk. wide, runs N.50°E., ascend steep hill, bears N.E. and S.W.
74.00	Leave dense undergrowth, thence through scattering timber.
80.00	<p>A point, 600 feet above the <math>\frac{1}{4}</math> sec. cor. and set an ironstone, 20x10x8 ins., 15 ins. in the ground, for cor. of secs. 31 and 32, and raised a mound of stone 2 ft. base, <math>1\frac{1}{2}</math> ft. high, N. of cor. Pits impracticable.</p> <p>The old cor. of secs. 31 and 32, as determined by the witness trees, described by the surveyor general, stone missing, bears S.82°W., 1 ch. 50 lks. dist. I destroy all traces of this old sec. cor.</p> <p>Land, mountainous.</p> <p>Soil, gravel and stone, 3rd and 4th rates.</p> <p>Timber, pine, fir and tamarack.</p> <p>Undergrowth, huckleberry, serviceberry, pine, fir, tamarack, willow, pine and bunch grass.</p> <p>Good pasturage.</p> <p>Mountainous land, 80.00 chs.</p>