

Resurvey of East Bdy. of T. 2 N., R. 37 E.

Chains	
	<p>true meridian with the solar at the cor. of Tps. 1 and 2 N., Rs. 37 and 38 E., which is a post firmly set marked and witnessed as described by the surveyor general, with the exception of the N.E. and N.W. bearing trees, which have entirely rotted away. I mark,</p> <p>A spruce, 16 ins. diam., bears N.60°E., 68 lks. dist., marked T 2 N., R. 38 E S 31 B T.</p> <p>A larch, 10 ins. diam., bears N.85°W., 32 lks. dist., marked T 2 N R 37 E S 36 B T.</p> <p>Thence I run</p> <p>N.0°15'E. on old township line between secs. 31 and 36. Ascend gradually along E. slope through heavy timber and dense undergrowth.</p>
39.70	<p>At 40.00 chs. minus 30 lks., the northering of the S. bdy. Set basalt stone, 15x10x8 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which,</p> <p>A fir, 10 ins. diam., bears S.71°W., 81 lks. dist., marked $\frac{1}{4}$ S 36 B T.</p>
40.34	<p>Intersect old $\frac{1}{4}$ sec. cor. which is a post badly decayed, marks obliterated and witnessed as described by the surveyor general. I destroy old post and set new fir post 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S 31 on E. face, from which the witness trees bear as stated by the surveyor general. I destroy all marks which pertain to the survey W.</p> <p>Thence I run</p> <p>N.0°17'E.</p>
51.00	Timber gradually becomes scattering, bears E. and W.
75.75	Spring branch, 2 lks. wide, in ravine 50 ft. deep, course S.80°E.
79.70	Intersect old cor. of secs. 25, 30, 31 and 36, which is a post badly rotted, marked and witnessed as described by the surveyor general, with the exception of the S.E. bearing tree, which has been destroyed.