

Resurvey of East Bdy. of T. 2 N., R. 37 E.

Chains	<p>47.00 Leave timber, bears E. and W.</p> <p>52.50 Summerville Trail bears N.70°W., S.70°E. Enter timber and undergrowth.</p> <p>55.00 Summit of divide between Grande Ronde Basin and Umatilla Basin, 300 ft. above creek, bears N.70°E., S.70°W. Descend along W. slope of divide.</p> <p>69.50 Creek, 3 lks. wide, in ravine, 150 ft. deep, course N.40°W. Ascend.</p> <p>78.69 Intersect old cor. of sec. 7, 12, 13 and 18, which is a post, badly decayed, marked and witnessed as described by the surveyor general. I destroy old post and set a basalt stone, 15x8x8 ins., 10 ins. in the ground, for cor. of secs. 7 and 18, marked with 2 notches on the N. and 4 notches on the S. edges. I destroy all marks pertaining to the survey W.</p> <p>Thence I run N.0°5'W.</p> <p>80.00 Set basalt stone, 15x10x6 ins., 10 ins. in the ground, for cor. of secs. 12 and 13, marked with 2 notches on the N. and 4 notches on the S. edges, from which, A fir, 12 ins. diam., bears S.76°W., 45 lks. dist., marked T 2 N R 37 E S 13 B T. A fir, 24 ins. diam., bears N.71°W., 53 lks. dist., marked T 2 N R 37 E S 12 B T.</p> <p>This cor. stands about 150 ft. below the summit of the divide.</p> <p>Land, mountainous. Soil, stony and loam, 3rd and 2nd rate. Timber, pine, fir and tamarack. Undergrowth, huckleberry, mountain laurel and small firs. Mountainous land, 80.00 chs.</p>
	<p>N.0°5'W. on old township line between secs. 7 and 12. Ascend S. slope of hill through heavy timber.</p>