

Resurvey of East Bdy. of T. 2 N. R. 37 E. W. M.

Chains	
	<p>Land, level and mountainous.</p> <p>Soil, rich loam and stony, 1st, 2nd 3rd rate.</p> <p>Timber, pine, fir and tamarack.</p> <p>Undergrowth, huckleberry, mountain laurel and small firs.</p> <p>Mountainous land, 79.87 chs.</p> <p>Overcast at noon prevented taking the latitude.</p> <p style="text-align: right;">July 10, 1901</p>
	<p>Survey of subdivisional lines of Township No. 2 North Range 37 East, Willamette Meridan Oregon, as surveyed by Charles L. Campbell, U.S. Deputy Surveyor, under contract No. 733 dated March 22, 1901.</p>
	<p>From cor. of Secs. 25, 30, 31 and 36, heretofore described. Thence I run W. on Sectional Correction Line bet. Secs. 25 and 36.</p> <p>Ascend E. slope of divide through scattering pine, and fir timber.</p>
20.61	A fir, 15 ins. diam., on line, I mark with 2 notches on E. and W. sides.
23.65	A fir, 28 ins. diam., on line, I mark with 2 notches on E. and W. sides.
40.00	<p>Set a fir post 3 ft. long 3 ins. sq. 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. 25 on N. face, and S. 36 on S. face, from which</p> <p>A fir, 30 ins. diam., bears N 31° E 134 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir 36 ins. diam., bears S 53° W 190 lks. dist., marked $\frac{1}{4}$ S B T.</p>
51.50	<p>Enter heavy timber, bears N. and S.</p> <p>Ascend gradually over rolling mountain prairie.</p>
62.50	Summit of divide, bet Grande Rounde Valley and Umatilla Valley, 300 ft. above Sec. cor. bears N. and S.
63.00	Trail to Bingham Springs, course N. and S.
64.00	Descend gradually.