

-91-

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	base, $1\frac{1}{2}$ Ft. high W. of cor., this being the most secure place for mound.
45.25	Foot of hill, 500 ft. below summit of divide
45.30	Thomas and Ruckel Fork of Umatilla River, 10 lks. wide, swift current, course N. 10° W.
	Ascend
56.00	Leave burn, bears N. and S. Enter scattering green timber.
58.50	Small creek, 4 lks. wide, course N. 40° E. Ascend E. slope of mountain.
63.50	Enter old burn, bears N. 20° E., S. 20° W.
65.00	Enter dense undergrowth, bears N. and S.
80.00	Set ironstone, 18x8x6 ins. 12 ins. in the ground, for cor. of Secs. 26, 27, 34 and 35, marked with 2 notches on E. and 1 notch on S. edges; from which A fir, 12 ins. diam., bears S $16\frac{1}{2}^{\circ}$ W. 80 lks. dist., marked T. 2 N R 37 E., S 34 B T. A fir, 12 ins. diam., bears N. 66° W. 201 lks. dist., marked T. 2 N R 37 E., S 27 B T. No other trees in limit; Raise mound of stone, 3 ft. base $1\frac{1}{2}$ ft. high, W. of cor. Pits impracticable! This cor. stands about 300 ft. above Thomas and Ruckel creek. Land, mountainous. Soil, stony and lean; 3rd and 2nd rate. Timber, pine, fir, tamarack and spruce. Undergrowth, small firs, mountain laurel and willows. Mountainous land, 80.00 chs.
	W. on Sectional Correction Line bet. Secs. 27 and 34, Ascend E. slope of mountain through dead timber and dense laurel thickets.
13.500	Leave laurel thickets, bears N. and S.
18.50	Mere gradual ascent.