

Chains 24.00	Enter scattering pine timber, bears N. 20° W., S. 20° E. Pass over prairie on summit of ridge.
40.00	Set ironstone, 20x10x14 ins. 15 ins. in the ground, for 1/4 Sec. cor. marked 1/4 on N. face, from which A spruce, 12 ins. diam., bears S. 11° E. 72 lks. dist., 1/4 S. 34 B T. A fir, 30 ins. diam., bears N. 79° W. 132 lks. dist., marked S 27 B T.
45.00	Descend gradually.
52.00	Enter heavy timber and undergrowth, bears N. 10° E., S. 10° W.
62.00	Dry bed of stream, course S. 40° W. Leave undergrowth.
69.00	Leave timber, bears N. and S. and enter rocky prairie.
75.00	Enter scattering timber, bears N. 10° W., S. 10° E.
80.00	Set basalt stone, 15x10x8 10 ins. in the ground, for cor. of Secs. 27, 28, 33 and 34 marked with 3 notches on E. and 1 notch on S. edges; from which A pine, 24 ins. diam., bears N. 74° E., 23 lks. dist., marked T 2 N R 37 E., S 27 B T. A fir, 16 ins. diam., bears S. 24° E 43 lks. dist., marked T 2 N R 37 E., S 34 B T. A fir, 20 ins. diam., bears S. 40° W. 84 lks. dist., marked T 2 N R 37 E., S 33 B T. A fir, 24 ins. diam., bears N. 74° W. 142 lks. dist., marked T 2 N R 37 E., S 28 B T.
	Land, mountainous. Soil, stony and sandy loam; 3rd and 2nd rate. Timber, pine, fir, tamarack and spruce. Undergrowth, willow, laurel, huckleberry and small firs. Mountainous land, 80.00 chs.