

Subdivisions of T. 2 N. R. 37 E.

Chains	
	Undergrowth, willows, laurel huckleberry and small firs. Mountainous or heavily timbered land 100.54 chs. July 16, 1901.
	From the cor. of Secs. 25, 26, 35 and 36, thence I run S 0° 01' E., on random line, bet Secs. 35 and 36.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
79.21	Intersect S bdy. of tps., 65 lks. E. of the cor. of Secs. 1, 2, 35 and 36. heretofore described. I destroy all marks on old cor. pertaining to the survey N. At the point of intersection I set ironstone, 15x12x6 ins. 10 ins. in the ground for closing cor. of Secs. 35 and 36 marked C C on N face, with 1 groove on E. and 5 grooves on W. faces; from which A fir, 30 ins. diam., bears N. 15° E., 46 lks. dist., marked T 2 N R 37 E., S 36 B T. A fir, 24 ins. diam., bears N. 14° W. 43 lks. dist., marked T 2 N R 37 E., S 35 B T. Thence I run N. 0° 01' W. on true line, bet Secs. 35 and 36. Ascend gradually through heavy timber.
5.50	Top of rise, bears E. and W. Descend gradually along W. slope of ridge.
39.06	A fir, 10 ins. diam., on line I mark 2 notches on N. and S sides.
39.21	Set fir post, 3 ft. long 4 ins. sq., 24 ins. in ground for, $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S 35 on W. and S 36 on E. faces; from which A fir, 10 ins. diam., bears N. 84° E., 23 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 12 ins. diam., bears S. 75° W. 23 lks. dist., marked $\frac{1}{4}$ S. B. T.
44.50	Enter scattering timber, bears E. and W.
53.10	Foot of ravine, 25 ft. deep course N. E.