

Subdivisions of T. 2 N. R. 37 E. W. M.

57.20	A fir, 24 ins. diam., on line I mark 2 notches on N. and S. edges.
69.00	Enter heavy timber and undergrowth, bears E. and W.
79.21	The cor. of Secs. 25, 26, 35 and 36. Land, level and mountainous. Soil, sandy loam; 2nd rate. Timber, pine, fir, tamarack and spruce. Undergrowth, small firs mountain laurel and huckleberry Mountainous or heavy timbered land. 79.21 chs. July 18, 1901.
	N. 0° 01' W. bet. Secs. 25 and 26. Descend gradually through heavy timber.
0.90	Trail to Bingham Springs, bears N. 20° E., S. 20° W.
5.75	Dry bed of stream, 10 lks. wide, course N. 40° W. Water sinks just E. of line.
16.50	Ascend gradually.
33.01	A fir, 36 ins. diam., on line I mark 2 notches on S. and N. sides.
40.00	Set fir post, 3 ft. long 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. 26 on W. and S 25 on E faces; from which A larch, 30 ins. diam., bears S. 75° E., 12 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 32 ins. diam., bears S. 20° W. 6 lks. dist., marked $\frac{1}{4}$ S B T. This $\frac{1}{4}$ cor. stands about 200 fts above the Sec. cor.
40.17	A fir, 18 ins. diam., on line I mark 2 notches on N. and S sides.
50.09	A fir, 18 ins. diam., on line, I mark 2 notches on N. and S. sides.
55.00	Leave timber, bears E. and W.
62.50	Enter heavy pine and fir timber and undergrowth, bears N. 70° W., S. 50° E.