

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains 79.30	<p>Pack trail, bears N. W. S. E.</p>
80.00	<p>Set fir post, 3 ft. long, 4 ins. sq., 24 ins in the ground, for cor. to Secs. 23, 24, 25 and 26, marked T 2 N. R 34 on N.E.R. of 37 E., S 25 on S E., S 26 on S W., and S 23 on N W faces; with 1 notch on E. and 2 notches on S edges; from which</p> <p>A larch, 36 ins. diam., bears N. 39° E., 58 lks. dist., marked T 2 N. R 37 E., S 24 B T.</p> <p>A larch, 18 ins. diam., bears S. 40° E. 34 lks. dist., marked T 2 N. R 37 E., S 25 B T.</p> <p>A larch 24 ins. diam., bears S. 31° W. 27 lks. dist., marked T 2 N R 37 E., S 26 B T.</p> <p>A larch, 38 ins. diam., bears N. 25° W. 32 lks. dist., marked T. 2 N. R 37 E., S 23 B T.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam; 1st and 2nd rate.</p> <p>Timber, fir, pine, larch, tamarack and spruce.</p> <p>Undergrowth mountain laurel and huckleberry.</p> <p>Mountainous or heavily timbered land, 80.00 chs</p>
	<p>E. on random line, bet. Secs 24 and 25</p>
40.00	<p>Set temp. <math>\frac{1}{4}</math> Sec cor.</p>
79.68	<p>Intersect E. bdv. of Tp; 10 lks. N. of the cor. of Secs. 24 and 25 established by me. July 1901; Thence I run N. 89° 56' W., on true line, bet. Secs. 24 and 25.</p> <p>Ascend over rolling land, through heavy timber.</p>
12.25	<p>Old Summerville Trail, bears N. 10° W., S. 10° E.</p>
13.40	<p>Creek, 5 lks. wide, swift current, pure water, course N. 10° W., S. 10° W.</p>
39.84	<p>Set basalt 15x12x5 ins. 10 ins. in the ground for <math>\frac{1}{4}</math> Sec. cor. marked <math>\frac{1}{4}</math> on N. Face; from which</p> <p>A tamarack, 28 ins. diam., bears S. 55° W; 11 lks. dist., marked <math>\frac{1}{4}</math> S 25 B T.</p> <p>A fir, 18 ins. diam., bears N. 51° W. 46 lks. dist., marked <math>\frac{1}{4}</math> S 24 B T.</p>