

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
24.00	Rocky ridge point, bears N. 30° W., S. 60° E. Descend into ravine.
37.50	Spring branch, 2 lks wide, in ravine 50 ft. deep, course N. 50° W. Ascend.
40.00	Set ironstone, 30x16x 4 ins. 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W face; from which A pine, 24 ins. diam., bears N. 46° E., 42 lks. dist., marked $\frac{1}{4}$ S 24 B T. A fir, 12 ins. diam., bears N. 25° W., 40 lks. dist., marked $\frac{1}{4}$ S 23 B T.
46.84	A tamarack, 30 ins. diam., on line, I mark with 2 notches on N and S sides.
53.75	Spring branch, 1 lk. wide, course N. 85° W. Enter dense undergrowth, bears N. 80° W., S. 80° E.
59.50	Leave heavy timber and dense undergrowth, bears N. W. S. E.
67.50	Enter heavy fir timber and dense undergrowth, bears E. and S.
72.75	Spring branch, 2 lks. wide, course W.
75.00	Leave heavy timber and dense Undergrowth, bears E. and W. Over bunch grass prairie.
80.00	Set ironstone, 20x10x5 ins., 10 ins. in the ground, for cor. of Secs. 13, 14, 23 and 24, marked with 1 notch on E. and 3 notches on S. edges; from which A fir, 24 ins. diam., bears N. 28° E. 228 lks. dist., marked T 2 N R 37 E S 13 B T. A pine, 24 ins. diam., bears N. 31° W. 227 lks. dist., marked T 2 N R 37 E S 14 B T. No other trees in limit. Raise mound of stone, 3 ft. base, $1\frac{1}{2}$ ft. high, W. of cor. Pits impracticable.
	Land, mountainous and level
	Soil, stony and loam, 3rd and 2nd rate.
	Timber, fir, pine, spruce and larch.
	Undergrowth, mountain laurel, huckleberry and willow.
	Mountainous or heavily timbered land. 75.00 chs.

July 19, 1901