

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
	S. 89° 56' E. on random line bet. Secs. 13 and 24.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
78.85	Intersect E. bdy. of Tp., 16 lks. N. of cor. Secs. 13 and 24. Established by me. July 1901.
	N. 89° 49' W. on true line bet. Secs. 13 and 24.
	Ascend through heavy fir and pine timber.
16.50	Ravine, 50 lks. deep, course S. 40° E.
32.25	Spring branch, 2 lks. wide, course S. 50° E.
38.85	Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S 13 on N. and S. 24 on S. faces; from which
	A tamarack, 24 ins. diam., bears N. 71° E., 23 lks. dist., Marked $\frac{1}{4}$ S B F.
	A fir, 24 ins. diam., bears S. 45° E., 67 lks. dist., marked $\frac{1}{4}$ S B T.
	More gradual ascent.
45.00	Summit of divide, bet. Grande Valley and Umatilla Valley, 300 ft. above Sec. cor. bears N. and S.
	Descend W. slope of divide.
49.00	Trail to Bringham Springs, bears N. 20° W. and S.
67.25	Leave timber, bears N. and S., over prairie.
78.85	The cor. of Secs. 13, 14, 23 and 24.
	Land mountainous and level.
	Soil, loam, 2nd rate.
	Timber, pine, fir, tamarack, spruce and larch.
	Mountainous or heavily timbered land. 70.00 chs.
	N. 0° 01' W., bet. Secs. 13 and 14.
	Over prairie.
2.00	Descend steep N. slope of hill, through scattering timber, bears E. and W.
7.50	Enter heavy timber, and undergrowth, bears N. 70° W., S. 70° E.
28.65	Spring branch, 1 lks. wide, course N. W.
29.10	Creek, 3 lks. wide, slow current, pure water, course N. W.
	Ascend.