

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	S. 89° 49' E. on random line bet. Secs. 12 and 13.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
79.30	Intersect E. bdy of Tp. 5 lks. N. of the cor. of 12 and 13, established by me. July, 1901. N. 89° 47' W. on true line bet. Secs. 12 and 13. Ascend E. slope of hill through heavy timber.
6.00	Leave timber, bears N. and S.
7.00	Top of hill 100 ft. above Sec. cor., bears N. and S.
13.50	Descend W. slope.
13.50	Enter heavy timber and dense undergrowth, bears N. and S.
20.05	Spring branch, 2 lks. wide, course N. 40° W., in ravine 100 ft. deep. Ascend.
29.00	Top of rocky ridge point 150 ft. above spring branch bears N. 30° W. Descend.
32.25	Spring branch, 2 lks. wide, in ravine 100 ft deep, course N. 10° W. Ascend, steep E. slope of divide
39.30	Set basalt stone, 15x12x4 ins. 10 ins. in the ground, for, $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on N. face, from which A pine, 36 ins. diam., bears N. 70° E., 71 lks. dist., marked $\frac{1}{4}$ S 12 B T. A fir, 30 ins. diam., bears S. 55° E., 48 lks. dist., marked $\frac{1}{4}$ S 13 B T.
39.75	Summit of ridge, 300 ft. above creek bears N. and S.
42.00	Descend steep W. slope through scattering timber, bears N. and S.
66.25	Creek 8 lks. wide, swift current, in canyon 500 ft. deep course, S. 15° W.
79.30	The cor. of Secs 11, 12, 13 and 14. Land, mountainous. Soil, stony and sandy loam; 3rd and 2nd rate. Timber, pine, fir, spruce larch and tamarack. Undergrowth, small fir thickets, huckleberry and mountain laurel. mountainous land, 79.30 chs.