

## Subdivisions of T. 2 N. R. 37 E. W. M.

Chains

N. 0° 01' W. bet. Secs. 11 and 12.

Ascend through scattering timber, along steep E. slope.  
of mountain.40.00 Set fir post, 3 ft. long 4 ins. sq., 24 ins. in ground for  
 $\frac{1}{4}$  Sec. cor. marked  $\frac{1}{4}$  S 11 on W. and S. 12 on E.  
faces, from which:A fir, 12 ins. diam., bears S. 85° E., 24 lks.  
dist., marked  $\frac{1}{4}$  S B T.A tamarack, 16 ins. diam., bears N. 40° W., 47 lks.  
dist. marked  $\frac{1}{4}$  S B T.

52.00 Enter heavy fir and pine timber, bears E. and W.

60.00 Leave timber, bears N. 30° E., S. 30° W.

65.00 Summit of divide bet. Buck Creek, and Thomas Ruckel

Fork Umatilla, 500 ft. above Sec. cor., bears E. and W.  
Thence along level mountain top.

69.50 Trail to Bingham Springs, course N. 40° E., S. 40° W.

80.00 Set ironstone, 15x10x4 ins. 10 ins. in the ground for  
cor. of Secs. 1, 2, 11 and 12, marked with 1 notch  
on E. and 5 notches on S. edges; from whichA fir, 48 ins. diam., bears N. 42° E., 43 lks.  
dist., marked T 2 N R 37 E., S 1 B T.A fir, 24 ins. diam., bears S. 40° E., 43 lks.  
dist., marked T 2 N R 37 E., S 12 B T.A tamarack, 36 ins. diam., bears S. 20° W. 42 lks.  
dist., marked T 2 N R 37 E., S 11 B T.A fir, 30 ins. diam., bears N. 74° W. 84 lks.  
dist., marked T 2 N R 37 E., S 2 B T.

Land mountainous and level.

Soil, sandy loam; 2d rate.

Timber, pine, fir, tamarack and spruce.

Mountainous land, 80.00 chs

July 20, 1901