

Subdivisions of T 2 N R 37 E. W. M.

Chains	Descend along slight W. slope through heavy timber and dense undergrowth.
18.35	Leave timber and undergrowth, bears N. and S.
19.70	A log cabin bears S. 15° E. about 7.00 chs. dist.
25.35	Ascend E. slope of hill
25.75	Enter heavy fir timber and dense undergrowth bears N. and S.
35.35	Leave timber and undergrowth bears N. 30° W., S. 30° E.
40.17	Set basalt stone; 15x7x7 ins. 10 ins. on the ground for $\frac{1}{4}$ sec. cor. marked on N. face, from which A fir, 18 ins. diam., bears S. 20° W. 40 lks. dist. marked $\frac{1}{4}$ S 26 B T. A pine, 30 ins. diam., bears N. 47° W., 23 lks. dist., marked $\frac{1}{4}$ S 23 B T.
41.00	Top of ridge, 300 ft. above Sec. cor. bears N. 30° W. and S.
42.50	Enter scattering pine and fir timber, bears N. and S. Descend steep S. W. slope of mountain
70.35	Thomas and Buckel Fork of Umatilla River, 15 lks. wide, swift current, in canyon on 800 ft. deep course N. 60° W. Ascend along steep N. slope of mountain, through heavy timber, bears N. W. S. E.
80.34	The cor. of Secs. 22, 23, 26 and 27 Land, mountainous and level. Soil, stony and loam; 3rd and 1st rate. Timber, fir, pine and tamarack. Undergrowth, mountain laurel, small firs, and huckleberry Mountainous or heavily timbered land, 80.34 chs.