

Subdivisions of T. 2 N. E. 37 E. W. M.

Chains	This cor. stands about 400 ft. above the creek.
55.00	Leave timber, bears N. and S.
63.00	Enter heavy timber, bears N. W. S. E.
65.00	Top of ridge, 800 ft. above creek, bears N. W. S. E.
77.25	Trail bears N. W. and S. E.
80.20	The cor. of Secs. 14, 15, 22 and 23.
81	Land, mountainous. Soil, stony and gravelly loam; 3rd and 2nd rate. Timber, fir, pine and tamarack. Undergrowth, huckleberry, laurel and vine maple. Mountainous land, 80.00 chs. July 25,
	N. 0° 02' W. bet. Secs. 14 and 15. Ascend along W. slope of mountain, through heavy timber.
10.50	Leave heavy timber, bears E. and W.
11.50	Enter scattering timber, bears E. and W.
17.50	Ridge point, 200 ft. above Sec. cor., bears E. and W. Steep descent into deep canyon.
34.00	Enter heavy timber, bears E. and W.
40.00	Set fir post, 3 ft. long, 3 ins. sq. 24 ins. in the ground for $\frac{1}{2}$ Sec. cor. marked $\frac{1}{2}$ S. 15 on W. and S. 14 on E. faces, from which A fir, 36 ins. diam., bears S. 75° E., 51 lks. dist., marked $\frac{1}{2}$ S B T. A fir, 30 ins. diam., bears S. 60° W., 21 lks. dist., marked $\frac{1}{2}$ S B T.
62.50	Steeper descent.
67.25	Spring branch, 1 lk. wide, course N. E.
75.75	Foot of hill, 1000 ft. below summit, bears E. and W.
76.00	Thomas and Ruckel Stage, bears N. 80° W., S. 80° E.
76.50	Creek, 20 lks. wide, swift current, pure water, sandy bottom, course N. 80° W.
76.75	Ascend steep S. slope of mountain.
80.00	Set basalt stone, 20x12x6 ins. 15 ins. in the ground for cor. of Sec. 10, 11, 14 and 15, marked with 2 notches on E. and 4 notches on S. edges; from which