

Subdivisions of T. 2 N., R. 37 E., W. M.

Chains	<p>This cor. stands about 250 ft. above $\frac{1}{4}$ Sec. cor. Land, mountainous. Soil, stony 3rd rate. Timber, pine, fir and tamarack. Mountainous land. 80.00 chs.</p>
	<p>N. 89° 49' E. on random line Sec. 2 an 11.</p>
40.00	<p>Set temp. $\frac{1}{4}$ Sec. cor.</p>
79.80	<p>Intersect N. and S. line 37 lks. N. of the cor. of Secs. 1, 2, 11 and 12.</p>
	<p>Thence I run N. 89° W. 55½ W. on true line bet. Secs. 2 and 11.</p>
	<p>Ascend gradually on mountain through heavy timber and undergrowth.</p>
7.50	<p>Descend gradually.</p>
114.00	<p>Foot of draw, 100 ft. deep, course N. Ascend.</p>
20.00	<p>Enter scattering timber, bears N. and S.</p>
24.00	<p>Divide bet. Umatilla River and Buck Creek, 1000 ft. high bears N. and S.</p>
	<p>Descend gradually.</p>
29.83	<p>Buck Mountain pack trail, bears N. W. and S. E.</p>
32.50	<p>Enter heavy timber, bears N. and S.</p>
39.90	<p>Set basalt stone, 20x12x4 ins., 15 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on N. face, from which A fir, 12 ins. diam., bears N. 2° E., 19 lks., dist. marked $\frac{1}{4}$ S 2, B T. A fir, 10 ins. diam., bears S. 73° W. 49 lks. dist., marked $\frac{1}{4}$ S 2 B T.</p>
43.50	<p>Leave timber and pass over bunch grass prairie, bears N. and S.</p>
54.00	<p>Descend gradually.</p>
63.00	<p>Steeper descent of W. slope.</p>
79.80	<p>The cor. of Secs. 2, 3, 10 and 11.</p>