

Subdivisions of T. 2 N. R. 37 E. W. M.

| Chains | |
|--------|---|
| | Raise mound of stone, 2 ft. base, 1½ ft. high, N. of cor. Pits impracticable. |
| 48.20 | Spring branch, 2 lks. wide, in ravine 75 ft. deep, course S. |
| 80.24 | The cor. of Secs. 10, 11, 14 and 15. Land, mountainous. Soil, stony; 3rd rate. Timber, fir and pine. Mountainous land. 80.24 chs. July 25, 1901. |
| | N. 0° 02' W. bet. Secs. 10 and 11. Ascend steep S. slope of mountain, through scattering timber. |
| 40.00 | Set ironstone, 20x8x6 ins., 15 ins. in the ground for ¼ Sec. cor., marked ¼ on W. face, from which A pine, 36 ins. diam., bears N. 41° E., 110 lks. dist., marked ¼ S 11 B.T. A pine, 30 ins. diam., bears S. 44° W., 120 lks. dist., marked ¼ S 10 B T. This cor. stands about 700 ft. above the creek. |
| 44.50 | Ridge point, 300 ft. high, bears E. and W., Descend through heavy timber, bears E. and W. |
| 56.00 | Dry bed of stream, 5 lks. wide, course W. Just about 5.00 chs. W. of this point there is a large ice cold spring. Leave timber bears E. and W. Ascend along W. slope of mountain. |
| 69.50 | Enter small patch of timber, bears E. and W. |
| 72.00 | Leave timber, bears E. and W. |
| 80.00 | Set basalt stone, 20x12x8 ins., 15 ins. in ground for cor. of Secs. 2, 3, 10 and 11, marked with 2 notches on E. and 3 notches on S. edges, Raise mound of stone, 3 ft. base, 2 ft. high, W. of cor. Pits impracticable. |