

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains 60.15	Foot of mountain, 500 ft. below summit of ridge, bears N. 75° E., S. 75° W.
	Ascend over rolling land sloping W.
71.00	Leave timber and undergrowth, bears E. and W.
71.50	Top of branch ridge, 300 ft. high, bears E. and W. Descend steep S. slope.
74.05	The cor. of Secs. 2, 3, 10 and 11. Land, level and mountainous. Soil, stony and gravelly loam; 3rd and 2nd rate. Timber, fir, pine, yew, larch, spruce and tamarack. Undergrowth, mountain laurel, vine maple, willow and small firs.
	Mountainous or heavily timbered land. 49.80 chs.
	July 26, 1901.
	S. 0° 03' E. on random line bet. Secs. 33 and 34.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
78294	Intersect S bdy. of tps. 72 lks. E. of the cor. of Secs. 3, 4, 33 and 34 heretofore, described. I destroy all marks on old cor. pertaining to the survey N. At the point of intersection set fir post 3 ft. long 4 ins sq., 24 ins. in the ground for closing cor. Secs. 33 and 34, marked C C T 2 N R 37 E., on N S 34 on E. and S 33 on W. faces; with 3 grooves on E. and W. faces; Raise mound of stone, 4 ft. base, 2 ft. high, N. of cor. Pits impracticable.
	Thence I run N. 0° 03' W. on true line bet. Secs. 33 and 34. Over rocky prairie.
15.25	Trail to Bingham Springs, bears N. 70° E., S. 70° W. Enter scattering timber, bears E. and W.
16.75	Divide bet. North Fork and Umatilla River, 10 ft. above closing cor., bears N. 10° W. S. 10° E.
	Descend.
23.25	Dense undergrowth, bears E. and W.