

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	<p>Land level and mountainous. Soil, gravelly loam; 1st and 2nd rate. Timber, fir, pine, larch, spruce, yew and tamarack. Mountainous or heavily timbered land, 14.00 chs.</p>
40.00	<p>N 0° 02' W. on random line bet. Sec. 2 and 3. Set temp. $\frac{1}{4}$ Sec. cor.</p>
74.05	<p>Intersect N. bdy. of Tp. 6.10 chs. E. of $\frac{1}{4}$ Sec. cor., which is a basalt stone, 5x10x4 ins. above ground, marked $\frac{1}{4}$ on N. face, from which A fir, 18 ins. diam., bears N. 20° E., 96 lks. dist., marked $\frac{1}{4}$ S335 B.T. At the point of intersection I set a stone, 18x10x5 ins. 12 ins. in the ground for closing cor. Secs. 2 and 3, marked D C on S., 2 groves on E. and 4 groves on W. faces, from which A fir, 12 ins. diam., bears S. 11° E. 25 lks. dist., marked T 2 N R 37 E., S 2 B T. A fir, 12 ins. diam., bears S. 25° W., 19 lks. dist., marked T 2 N R 37 E., S 3 B T.</p>
16.25	<p>Thence I run S. 0° 02' E. on true line bet. Secs. 2 and 3. Ascend steep N slope of mountain through heavy timber and dense undergrowth. Leave timber and undergrowth, bears E. and W. N. side of mountain prairie, bears E. and W. Over nearly level ground.</p>
25.95	<p>Buck Mt. pack trail, bears E. and W.</p>
33.25	<p>Summit of divide bet. Buck Creek and Umatilla River, 1000 ft. above Umatilla River, bears E. and W. Descend.</p>
34.05	<p>Set basalt stone, 20x10x4 ins. 15 ins. in the ground for Sec. cor. marked $\frac{1}{4}$ on W. face, Raise mound of stone, 3 ft. base, 2 ft. high, W. on cor. Pits impracticable.</p>
43.00	<p>Steeper descent of S. slope of mountain.</p>
47.25	<p>Enter timber and dense undergrowth, bears N. W. and S.E.</p>