

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
4.50	Foot of hill, 100 ft. below Sec. cor. bears N. 60° W., S. 60° E.
4.55	Old Thomas and Ruckel Stage Road, bears N. 60° W., S. 60° E.
5.80	Creek, 15 lks. wide, swift current, course N. 60° W. Ascend abruptly along N. W. slope; mountain bears N. W. S. E.
19.50	Mere gradual ascent. Enter scattering timber, bears N. and S.
29.50	Top of ridge point, 800 ft. above creek, bears N. W. S. E. Descend W. slope.
29.90	Trail, bears N. W. S. E.
40.12	Set ironstone, 15x12x4 ins., 10 ins. in the ground, for $\frac{1}{2}$ Sec. cor. marked $\frac{1}{2}$ on N. face, from which A fir, 30 ins. diam., bears S. 10° E., 71 lks. dist., marked $\frac{1}{2}$ S 15 B T. A fir, 24 ins. diam., bears N. 18° W., 24 lks. dist., marked $\frac{1}{4}$ S 10 B T. This cor. stands about 200 ft. below top of hill.
51.00	Foot of mountain., 600 ft. below top of ridge. Enter heavy timber and dense undergrowth, bears N. and S.
51.60	Thomas and Ruckel Creek, 25 lks. wide, swift current, sandy bottom, course N. 10° W. Ascend steep E. slope.
61.75	Enter scattering timber bears N. and S.
65.75	Enter dense fir thicket, bears N. and S.
74.00	Leave thicket, bears N. W. S. E.
80.24	The cor. of Secs. 9, 10, 15 and 16. Land, mountainous. Soil, stony; 3rd rate. Timber, fir, tamarack, pine and cottonwood. Undergrowth, mountain laurel, huckleberry, yew and small firs. Mountainous land. 80.24 chs.