

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
	N. 0° 03' W. bet, Secs. 9 and 10.
	Descend gradually along E. slope, through scattering timber
	and undergrowth.
4.50	Enter dense fir thicket bears E. and W.
15.00	Dry bed of stream, 10 lks. wide, course N. 60° E.
	Leave thicket, bears E. and W. and ascend.
30.00	Top of ridge, 300 ft. high, course E. and W.
	Descend steep N. slope of mountain.
40.00	Set ironstone, 20x12x8 ins., 15 ins. in the ground, for
	1/2 Sec. cor., marked 1/2 on W. face, from which
	A fir, 10 ins. diam., bears N. 10° E., 28 lks.
	dist., marked 1/2 S 10 B T.
	A fir, 8 ins. diam., bears S. 17° W., 16 lks.
	dist., marked 1/2 S 9 B T.
53.00	Over irregular bluffs 50 ft. high bears E. and W.
56.00	Spring branch, in ravine, 100 ft. deep, course N. 60° E.
64.50	Foot of mountain, 1000 ft. below ridge points, bears N.
	W., S. E.
65.35	Thomas and Ruckel Creek, 25 lks. wide, course N. 40° W.
	Over bottom lands not subject to inundation.
67.00	Thomas and Ruckel Stage Road, bears N. W., S. E.
69.00	Ascend S. slope of mountain.
79.25	Leave undergrowth, bears E. and W.
80.00	Set ironstone, 20x12x8 ins., 15 ins. in the ground for
	cor. of Secs. 3, 4, 9 and 10, marked with 3 notches
	on E. and 5 notches on S. edges; from which
	A pine, 12 ins. diam., bears S. 30° E. 121 lks.
	dist., marked T 2 N R 37 E. S. 10 B T.
	A fir, 24 ins. diam., bears S. 40° W., 88 lks.
	dist., marked T 2 N R 37 E., S. 9 B T.
	A pine, 18 ins. diam., bears N. 79° W., 143 lks.
	dist., marked T 2 N R 37 E., S 4 B T.