

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains No other trees in limits. Raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, W. of cor. Pits impracticable.
Land, mountainous.
Soil, sandy and stony, 3rd rate.
Timber, fir, pine, cottonweed and tamarack.
Undergrowth, small firs, huckleberry and mountain laurel.
Mountainous land, 80.00 chs.

July 29, 1901.

E. on random line bet. Secs. 3 and 10.

40.00 Set Temp. $\frac{1}{4}$ S cor.
79.85 Intersect N. and S. line 42 lks. N. of the cor. of Secs. 2, 3, 10 and 11.
Thence I run N. $89^{\circ} 42'$ W. on true line bet. Secs. 3 and 10.
Descend steep S. slope of mountain.
6.00 Enter scattering timber and undergrowth bears N. and S.
15.00 Perpendicular bluff 40 ft. high.
16.75 Dry bed of stream, 5 lks. wide, in canyon 500 ft. deep, course S. 20° W.
Water sinks just N. of line.
Ascend steep E. slope of branch ridge.
24.00 Leave timber and undergrowth, bears N. and S.
35.00 Ridge point, 300 ft. high, bears N. 10° E., S. 10° W.
Descend along S. slope, mountain bears E. and W.
39.92 $\frac{1}{2}$ Set ironstone, 18x8x3 ins., 12 ins. in the ground for $\frac{1}{2}$ Sec. cor. marked \odot on NN face. Raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N. of cor. Pits impracticable.
79.85 The cor. of Secs. 3, 4, 9 and 10.
Land, mountainous.
Soil, stony and gravelly loam; 3rd and 2nd rate.
Timber, fir, and pine.
Undergrowth, wild cherry and laurel.
Mountainous land, 79.85 chs.