

Subdivisions of T. 2 N. R 37 E. W. M.

Chains.	
79.88	<p>The cor. of Secs. 20, 21, 28 and 29.</p> <p>Land mountainous.</p> <p>Soil, loam and stony. 1st and 3rd rate.</p> <p>Timber, fir, pine, cottonwood and spruce.</p> <p>Undergrowth, very scattering patches of mountain laurel.</p> <p>Mountainous or heavily timbered land, 79.88 chs.</p>
	<p>N. 0° 04' W. bet Secs. 20 and 21.</p> <p>Descend along steep E. slope of mountain, through heavy timber.</p>
0.25	Foot of mountain, 800 ft. below ridge, Over level lands.
1.85	<p>Creek, 15 lks. wide, course N. 20° W.</p> <p>Ascend along steep W. slope, mountain bears N. 20° W., S. 20° E.</p>
33.00	Enter scattering timber, bears E. and W.
40.00	<p>A pine, 20 ins. diam., for $\frac{1}{4}$ Sec. cor. I mark $\frac{1}{4}$ S. 20 on W. and S. 21 on the E. faces; from which</p> <p>A fir, 20 ins. diam., bears N. 54° E., 35 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir, 24 ins. diam., bears N. 70° W., 50 lks. dist., marked $\frac{1}{4}$ S B T.</p>
	This cor. stands about 400 ft. above the creek.
72.00	<p>Spring branch, 2 lks. wide, course W.</p> <p>Ascend abruptly.</p>
80.00	<p>The point for Sec. cor. to Secs 16, 17, 20 and 21, falls on rock in place, 4, 2x1 ft. above ground. on which</p> <p>Cut a cross at the exact cor. point, for cor. of Secs. 16, 17, 20 and 21, marked with 4 notches on E. and 3 notches on S. edges, from which</p> <p>A pine, 30 ins. diam., bears N. 45° E., 95 lks. dist., marked T 2 N R 37 E., S 16 B T.</p> <p>A pine, 40 ins. diam., bears S. 70° E. 47 lks. dist., marked T 2 N R 37E., S 21 B T.</p> <p>A fir, 16 ins. diam., bears S. 89° W., 38 lks. Dist., marked T 2 N R 37 E., S 20 B T.</p>