

Subdivisions of T. 2 N. E. 37 E. W. M.

Chains	<p>Land, mountainous.</p> <p>Soil, stony and gravelly loam; 3rd and 2nd rate.</p> <p>Timber, fir, pine, spruce, yew and tamarack.</p> <p>Mountainous land, 80.30 chs.</p>
	<p>N. 0° 04' W. bet. Secs. 16 and 17.</p> <p>Ascend along steep W. slope of mountain, through scattering timber and undergrowth.</p>
9.15	Over perpendicular bluffs, 30 ft. high, bears E. and W.
21.00	Leave undergrowth, bears N. E. and S. W.
40.00	<p>Set ironstone, 20x18x6 ins., 15 ins. in the ground, for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on W. face; from which</p> <p>A fir, 12 ins. diam., bears S. 15° E., 32 lks. dist., marked $\frac{1}{4}$ S 16 B T.</p> <p>A fir, 20 ins. diam., bears N. 20° W., 71 lks. dist., marked $\frac{1}{4}$ S 17 B T.</p>
50.75	Enter heavy pine timber, bears N. 30° W., S. 30° E.
55.00	Foot of ravine, 150 ft. deep, course N. 60° W.
66.50	More gradual ascent.
70.75	Pack trail, bears N. 30° W., S. 30° E.
71.50	Over nearly level ground on W. slope of Chimney Horn Ridge bears N. 30° E., S. 10° E.
80.00	<p>Set basalt stone, 10x12x8 ins., 10 ins. in the ground for cor., of Secs. 8, 9, 16 and 17, marked with 4 notches on E. and 4 notches s. edges; from which</p> <p>A fir, 12 ins. diam., bears N. 73° E. 10 lks. dist., marked T 2 N R 37 E., S 9 B T.</p> <p>A fir, 29 ins. diam., bears S. 62° E., 28 lks. dist., marked T 2 N R 37 E., S 16 B T.</p> <p>A tamarack, 28 ins. diam., bears S. 63 lks. W. dist., marked T 2 N R 37 E., S 17 B T.</p> <p>A fir, 11 ins. diam., bears N. 24° W., 53 lks. dist., marked T 2 N. R. 37 E., S 8 B T.</p> <p>This cor. stands about 500 ft. above the Sec. cor.</p>