

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains.

and 2 grooves on S. faces, from which

A fir, 10 ins. diam., bears N. 21° E., 69 lks.

dist., marked T 2 N R 37 E., S. 19 B T.

A fir, 36 ins. diam., bears S. 43° E., 63 lks.

dist., marked T 2 N R 37 E., S 30 B T.

Thence I run E. on true line bet. Secs. 19 and 30.

Descend steep E. slope through heavy timber, and dense undergrowth.

91.10 Foot of mountain, 250 ft. below closing cor. S. Fork Umatilla River, 10 lks. wide, slow current, course N. 10° W.

Ascend steep W. slope of mountain.

30.00 Leave timber and undergrowth, bears N. and S.

41.00 Top of ridge, 1000 ft. above Umatilla River, bears N. 15° W., S. 15° E.

45.25 Enter heavy timber and undergrowth, bears N. and S.

47.10 A tamarack, 40 ins. diam., on line, I mark with 2 notches on E. and W. edges.

63.00 Creek, 3 lks. wide, course N. W.

60.65 Set ironstone, 15x10x5 ins. 10 ins in the ground for

$\frac{1}{4}$  Sec. cor., marked  $\frac{1}{4}$  on N. face from which

A fir, 30 ins. diam., bears S. 20° E., 80 lks.

dist., marked  $\frac{1}{4}$  S 30 B T.

A fir, 36 ins. diam., bears N. 75° W., 23 lks.

dist., marked  $\frac{1}{4}$  S 19 B T.

94.50 Leave timber, and undergrowth, bears N. and S.

100.65 The cor. of Secs. 19, 20, 29 and 30.

Land, mountainous.

Soil, stony and loam; 3rd and 2nd rate.

Timber, fir and pine, some tamarack.

Undergrowth, huckleberry and mountain laurel.

Mountainous land, 100.65 Chs.

July 5, 1901.