

Subdivisions of T. 2 N R 37 E. W. M.

Chains.	
	<p>dist., marked T 2 N R 37 E., S 6 B T.</p> <p>Thence I run S 0° 05' E. on true line, bet. Secs. 5 and 6.</p> <p>Ascend gradually.</p>
4.50	<p>Enter heavy timber, bears N. E., S. W.</p> <p>Ascend steep N. slope.</p>
21.00	<p>Top of ridge, 200 ft. above closing cor., bears E. and W.</p> <p>Descend through scattering timber bears E. and W.</p>
29.15	<p>Ravine, 100 ft. deep, course E.</p> <p>Ascend N. slope of ridge.</p>
35.25	<p>Set ironstone, 24x10x4 ins., 18 ins. in the ground, for $\frac{1}{2}$ Sec. cor., marked $\frac{1}{2}$ on W. face, from which</p> <p>A fir, 18 ins. diam., bears S. 60° E., 29 lks. dist., marked $\frac{1}{2}$ S 5 B T.</p> <p>A fir, 12 ins. diam., bears N. 33° W., 25 lks. dist., marked $\frac{1}{2}$ S. 6 B T.</p>
41.00	<p>Top of branch ridge, 150 ft. high, bears E. and W.</p> <p>Descend along steep S. E. slope, mountain bears N. 50° E., S. 30° W.</p>
70.00	<p>Enter heavy timber bears N. E. and S. W.</p>
71.00	<p>Foot of mountain, 300 ft. below ridge.</p>
73.25	<p>S. Fork Umatilla River, slow current, stony bottom, 50 lks. wide, course N. 60° E., S. 10° W.</p> <p>Over bottom not subject to inundation.</p>
74.75	<p>Ascend steep W. slope of mountain.</p>
75.25	<p>The cor. of Secs. 5, 6, 7 and 8.</p> <p>Land, mountainous.</p> <p>Soil, stony and gravelly loam; 3rd 4th and 2nd rate.</p> <p>Timber, fir, pine, spruce, larch and tamarack.</p> <p>Mountainous land, 75.25 chs. August 8, 1901</p>

General Description

Township 2 North, Range 37 East. contains a great variety of lands. There are several small meadows of rich alluvial soil along the South Fork of Umatilla River in sections 5, 6, and 7.