

Exterior Bdys. T.2 S., R.31 E., W.M.

Chains		Feet
	Land; very hilly. Soil; 3rd rate.	
	N. on E. Bdy. of Sec. 25. Descend hill. Var. $18\frac{1}{2}^{\circ}$ E.	
5.00	Foot of hill.	- 10
19.00	Creek, 6 lks. wide, runs N.E. Ascend.	
40.00	Set stone, 12 x 10 x 8 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 24 x 15 x 8 ins., for Cor. to Secs. 24, 25, 19 and 30.	+ 50
	Land; rough and broken. Soil; 2nd rate. Some balm timber on the creek.	
	N. on E. Bdy. of Sec. 24. Ascend hill. Var. $17\frac{1}{2}^{\circ}$ E.	
30.00	Top of hill on E. slope. Descend.	+ 15
40.00	Set stone, 18 x 10 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 18, 19, 13 & 24, in mound of earth, with charred stake, pits, trench, etc., as per instructions.	--50
	Land; hilly. Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 13. Var. $18^{\circ}30'$ E.	
1.50	Foot of hill	- 50
7.65	Creek, 6 lks. wide, runs N.W.	
16.10	Road brs. N.W. & S.E. Ascend hill.	
40.00	Set stone, 48 x 18 x 5 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 20 x 8 x 6 ins., for Cor. to Secs. 12, 13, 7 and 18 on top of hill.	+ 40
	Land; hilly. Soil; 2nd rate.	