

Subdivisional Lines, T. 2 S., R. 31, E., W.M.

Chains		Feet
	E. on a random line bet. Secs. 4 & 9.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line, 70 lks. S. of Cor. to Secs. 3, 4, 9 & 10, from which Cor., I run	
	S.89° 30' W. on a true line bet. Secs. 4 & 9.	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
79.80	The Cor. to Secs. 4, 5, 8 & 9. Land; level. Soil; 1st rate.	
<hr/>		
	N. on a random line bet. Secs. 4 & 5.	
	Var. 18 $\frac{1}{2}$ ° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect N. Bdy., 60 lks. E. of Cor. to Secs. 4 & 5, from which, I run	
	S.0°26' E. on a true line bet. Secs. 4 & 5.	
40.80	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with marked stone and pits, etc., as per instructions.	
80.80	The Cor. to Secs. 4, 5, 8 & 9. Land; level. Soil; 1st rate.	
<hr/>		
	N. bet. Secs. 31 & 32.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set stone, 18 x 12 x 9 for Cor. to Secs. 29, 30, 31 & 32. Land; level. Soil; 1st rate.	
<hr/>		
	E. on random line bet. Secs. 29 & 32.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 63 lks. N. of Cor. to Secs. 28, 29, 32 & 33, from which Cor. I run	
	N.89° 33' W. on true line bet. Secs. 29 & 32. Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
46.65	Foot of hill, brook, 3 lks. wide, runs N. Ascend hill.	-400
80.00	The Cor. to Secs. 28, 29, 32 & 33.	+300