

Subdivisinal Lines, T.2 S., R.31 E., W.M.

Chains		Feet
	Land; hilly. Soil; good 2nd rate.	
	W; on a random line bet. Secs. 30 & 31.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.70	Intersect W. Bdy. at Cor. to Secs. 30 & 31, from which I run	
	E. on a true line bet. Secs. 30 & 31. Descend hill.	
32.58	Brook, 3 lks. wide, runs N. Foot of hill. Ascend.	
40.70	Set stone, 18 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
80.70	The Cor. to Secs. 29, 30, 31 & 32. Land; rolling. Soil; 1st rate.	
	N. bet. Secs. 29 & 30. Var. $18\frac{1}{2}^{\circ}$ E.	
40.00	Set stone, 18 x 10 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 22 x 8 x 8, for Cor. to Secs. 19, 20, 29 & 30. Land; level. Soil; 1st rate.	
	E. on a random bet. Secs. 20 & 29.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. & S. line, 53 lks. N. of Cor. to Secs. 20, 21, 28 & 29, from which, I run	
	N. $89^{\circ} 37'$ W. on true line bet. Secs. 20 & 29. Descend hill.	
30.00	Foot of hill. Brook, 3 lks. wide, runs N. Ascend. House brs. S., 400 lks. dist.	200
40.20	Set stone, 15 x 7 x 7, for $\frac{1}{4}$ Sec. Cor.	
65.00	Top of hill	300
80.40	The Cor. to Secs. 19, 20, 29 & 30. Land; rolling. Soil; good 2nd rate.	
	W. on random line bet. Secs. 19 & 30.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect W. Bdy. at Cor. to Secs. 19 & 30, from which, I run	
	E. on a true line bet. Secs. 19 & 30. Descend hill.	